the container guy mob +64 21 968 816 Auckland / New Zealand www.thecontainerguy.co.nz



# 20' Standard Container Conversion Kit

Converts a standard 20' shipping container into a strong, durable, insulated, weatherproof office or accommodation unit.



20'GP with insulated lining panels, commercial fire rated steel door and 2 x PVC windows c/w security bars.



#### **Components**

- 19 x EPS insulated sandwich panels 2" (50mm) thick, double sided metal faced 0.0476mm steel Colourbond sheet, tongue and grooved slip fit.
- 14 x wall lining panels, self supporting.
- 5 x roof (ceiling) panels, self supporting.
- PVC window, American style, 3'H (912mm) x 4'W (1215mm), dual pane (double glazed), 1 x fixed pane, 1 x sliding pane, insect screen
- Steel window frame 4" x 2" RHS (100mm x 50mm) c/w 7 x 3/4" (20mm) solid security bars
- Heavy duty steel commercial 3 hour fire rated man door, 0.8mm steel skin, 36"W (908mm) x 80"H(2032mm). Aluminium threshold plate
- Heavy duty door hard ware, handle, dead lock, door shoe
- Heavy duty pre hung door frame. 2mm weld plate.
- PVC mouldings for securing the panels inside the container.
- 2 x Twin 4' (1.2m) energy efficient LED tube lights

#### **Easy installation**

- 1. Steel work. Mark out and cut openings in the container for the window(s), door, A/C etc. Position and weld in frames.
- 2. Prepare the surface and paint the container.
- 3. Install the 19 EPS insulated wall and roof panels along with the electrical cables. Fit and secure the PVC mouldings. Install the window, door, AC etc.
- 4. Qualified electrician finishes off the power connections, lights, etc
- 5. Container conversion is completed and ready for service.



Electrical cables are pre positioned and taped to the vertical corrugations that act as a conduit.





## **Optional**

- Steel A/C frames
- Additional windows
- High cube conversion kits
- Bathrooms

### **Shipping**

22 x 20'TEU standard conversion kits can be loaded in a 40'HC container. This container can also be purchased as part of the order to add the benefit of not having to unload on arrival.

Acts as the panel's storage.



#### **Accommodation units**



#### **Detention cells**



Built from a new 40'HC. The unit has a separation wall and has 2 x 4 man capacity with built in institutional stainless steel toilets.



## Laboratory



40'HC built into a laboratory with a securable storage area. Cargo doors are insulated and operational.